



Georgetown Charter Township

1515 Baldwin St., Jenison, MI 49428

Mining Board Meeting Agenda

August 19, 2020, after the Planning Commission meeting

1. THE PLANNING COMMISSION/MINING BOARD OF THE TOWNSHIP OF GEORGETOWN OTTAWA COUNTY, MICHIGAN

**NOTICE OF PUBLIC MEETING OF THE MINERAL MINING BOARD
OF GEORGETOWN TOWNSHIP VIA ELECTRONIC MEANS IN ACCORDANCE WITH
EXECUTIVE ORDERS 2020-154 AND 2020-160**

PUBLIC NOTICE is hereby provided that, in order to comply with recommended guidance from the U.S. Centers for Disease Control and Prevention (CDC) and Section I.1(a) of Executive Order 2020-154 issued by Governor Whitmer on July 17, 2020, amending the Open Meetings Act to allow a meeting of a public body to take place electronically, and pursuant to, Section 7.a(3) of Executive Order 2020-160 issue by Governor Whitmer on July 29, 2020, declaring indoor events among persons not part of a single household are permitted, but may not exceed 10 people, and in an effort to reduce the likelihood of spreading the Coronavirus (Covid-19), the Georgetown Township Mineral Mining Board will conduct the August 19, 2020, Mineral Mining Board meeting via electronic means using ZOOM on-line video conferencing immediately following the Planning Commission meeting which is scheduled to start at 7 PM.

The public may participate in the August 19, 2020, Mineral Mining Board meeting electronically via the following website address:
<HTTPS://US02WEB.ZOOM.US/J/81077190479>

Detailed instructions for joining the video conference of the meeting and providing public comment via video conference are included below.

PUBLIC NOTICE IS FURTHER PROVIDED THAT, in order to comply with Executive Order 2020-160, MEMBERS OF THE PUBLIC WILL NOT BE PERMITTED TO ATTEND THE MINERAL MINING BOARD MEETING AT THE GEORGETOWN TOWNSHIP OFFICE IN-PERSON.

In all other respects, the August 19, 2020, Mineral Mining Board meeting will be held in accordance with Michigan's Open Meetings Act.

Emails for the Mineral Mining Board may be directed to:

Mannette Minier, Mining Official, at MMINIER@GEORGETOWN-MI.GOV

This notice was posted at the Township Office on August 12, 2020 at

approximately 12:00 p.m. and on the Township's website, WWW.GEORGETOWN-MI.GOV, on August 12, 2020 at approximately 12:00 p.m.

To join the Mineral Mining Board meeting follow these instructions:

When: August 19, 2020, to start immediately following the Planning Commission Meeting (which has a 7 PM start time)

Topic: Georgetown Township Mineral Mining Board Meeting

Please click the link below to join the webinar:

[HTTPS://US02WEB.ZOOM.US/J/81077190479](https://us02web.zoom.us/j/81077190479)

Or iPhone one-tap :

US: +13126266799,,81077190479# or +19292056099,,81077190479#

Or Telephone:

US: +1 312 626 6799 or +1 929 205 6099 or +1 301 715 8592 or +1 346 248 7799 or +1 669 900 6833 or +1 253 215 8782

Webinar ID: 810 7719 0479

For those needing TTY Service, please contact Michigan Relay Services at 7-1-1 and provide them with one of the phone numbers above as well as the Webinar ID.

Members of the public will be given the option to provide comment during the Public Comment portion of the agenda. Those interested in providing comment will simply need to utilize the raise hand option at the appropriate time. To utilize the Raise Hand feature, follow these steps:

Those that have joined electronically: Click on Participants on the Control Panel at the bottom of the screen. The Raise Hand feature will be available in the lower right corner of the Participants box.

Those that have joined by phone: Push *9

2. NOTICE OF PUBLIC MEETING GEORGETOWN TOWNSHIP 1515 Baldwin Street Jenison, Michigan

Notice is Hereby Given, that in accordance with Act 184 of Public Act of 1943, as amended, the Georgetown Township Mineral Mining Board will hold a public meeting on Wednesday, August 19, 2020, after the Planning Commission meeting which starts at 7:00 p.m., or after, at the Georgetown Township Office, 1515 Baldwin Street, Jenison, Michigan, for consideration of applications for mineral mining license renewals for:

(ML2002) Renewal of (ML1502) – Ottawa County Road Commission

(ML2003) Renewal of (ML1504) – Huizinga Gravel

And any other business that would come before the board. Written comments will be received at the Township Office during regular office hours prior to the date of the hearing.

Richard VanderKlok, Clerk
Georgetown Charter Township

Posted: 4:00 p.m., Thursday, July 23, 2020

3. Call To Order
4. Roll Call
5. Approval Of The Agenda
6. Approval Of The Minutes Of The Previous Meeting
7. Bend In The River Plan Information

Documents:

[2010 BEND AREA FINAL REPORT REDUCED1.PDF](#)
[BEND AREA POTENTIAL ACQUISITIONS 8.5 X 11.PDF](#)
[HUIZENGA PROPOSED PURCHASE.PDF](#)
[CONCEPTUAL PLAN.PDF](#)

8. (ML2002) Renewal (ML1502) Ottawa County Road Commission - 1551 Taylor St.

- 8.I. (ML2002) Ottawa County Road Commission Staff Report

Documents:

[\(ML2002\) OTTAWA COUNTY ROAD COMMISSION STAFF REPORT.PDF](#)

9. (ML2003) Renewal (ML1504) Huizinga Gravel - 1861 Fillmore

- 9.I. (ML2003) Huizinga Gravel Staff Report

Documents:

[\(ML2003\) HUIZINGA STAFF REPORT.PDF](#)

- 9.II. Additional Information

Documents:

[HUIZINGA DETAILS.PDF](#)
[HUIZINGA MINING PLAN COMPLETE.PDF](#)
[HUIZINGA MINING PLAN.PDF](#)
[HUIZINGA PHASING PLAN.PDF](#)

10. Communications, Letters And Reports

11. Public Comments

12. Other Business

12.I. Note: The Boynton Mining License Has Expired; However, No More Mining Is Taking Place, The Land Has Been Reclaimed And Turned Over To The Ottawa County Parks.

12.II. 2019-2020 Inspections

Documents:

[2019 INSPECTIONS.PDF](#)

13. Adjournment

Bend Area Mining Site Master Plan Report



2010

Prepared by:



BAUER-FORD RECLAMATION
Division of Landscape Architects & Planners, Inc.

TABLE OF CONTENTS

Acknowledgements	p. 2
Introduction	p. 2
Existing Conditions	p. 3
Inventory and Analysis	p. 4
Design Development	p. 4
Estimated Cost Analysis	p. 5
Conclusion	p. 6
Analysis Maps	
Slope Analysis Map.....	p. 7
Soil Boring Location Analysis Map.....	p. 8
Standard Reclamation Plan (Per Township Ordinance)	
Areas of Non-Compliance.....	p. 9
Rough Grading Plan for remainder of site.....	p. 10
Grading Quantities and Costs for remainder of site.....	p. 11
Topsoil/Seeding Quantities and Costs for remainder of site.....	p. 12
Phasing Plan.....	p. 13
Park Development Reclamation Plan	
Park Master Plan.....	p. 14
Rough Grading Plan.....	p. 15
Reclaimed Slope Sections.....	p. 16
Picnic Shelter Site Plan Details.....	p. 17
Grading Quantities and Costs.....	p. 18
Topsoil/Seeding Quantities and Costs.....	p. 19
Phasing Plan.....	p. 20
Land Acquisition Map.....	p. 21
Alternate Development Options	
Concept 1.....	p. 22
Concept 2.....	p. 23
Concept 3.....	p. 24
Estimated Cost Comparison	P. 25

Acknowledgements

Bauer-Ford Reclamation (BFR) would like to acknowledge the following for their support and contributions to the 2009 Bend Area Mining Site Master Plan Report:

- Ottawa County Parks and Recreation Commission
- Ottawa County Road Commission
- Grand Rapids Gravel Company
- DeWent Gravel Company
- Huizenga Gravel Company

Introduction

The Bend Area mining site is located in Georgetown Township, Ottawa County, MI. The site continues to be mined for sand and gravel. The proposed park site is still owned by multiple property owners including: Huizenga Gravel Company, Nate Boyton, Grand Rapids Gravel Company (GRG), DeWent Gravel and the Ottawa County Road Commission (OCRC). The many stakeholders involved in this project continues to create challenges that will need to be overcome to achieve the vision of a cohesive county park, outlined in the 2000 "Bend Area Master Plan" approved by Georgetown Township. Although the Parks Commission has been successful in acquiring portions of the land from Nate Boyton, negotiations need to continue between the remaining property owners and Ottawa County Parks and Recreation Commission (OCPRC) to achieve the vision outlined in the plan.

Nate Boyton sold portions of his land to the OCPRC in 2008. The north portion lies between the Grand River and the inland lake that Mr. Boyton created. In addition, roughly 40 acres west of 12th Avenue was also sold by Mr. Boyton to the OCPRC. This area was determined to be a regulated wetland by the MDEQ.

The Huizenga land (western parcel) continues to be mined; however, at a very slow pace. Recent conversations with the landowners indicated it could be many years into the future before this land will become available for purchase; although, there was some indication that a portion of the land adjacent to the Grand River might become available sooner, if a deal could be negotiated.

The DeWent property, excluding the wooded wetland forming a long, finger-shaped parcel running northwest from 12th Street, is currently being mined under an agreement with GRG. This wooded wetland was determined to be a regulated wetland, and is therefore protected by the MDEQ. GRG had projected that it would complete mining in 2010 / 2011; until the recession caused them to alter their plans and at present it might be 2012 or 2013 before mining on the DeWent property is complete.

Grand Rapids Gravel Company is also operating on land leased from the Ottawa County Road Commission in order to mine, process and haul material. It is located southwest of the DeWent property in addition to the land they occupy immediately west of the DeWent property. Numerous meetings with GRG were held during this process to discuss how the active mining operation could be used to provide a unique opportunity in creating landscape features that would add to the recreation value of the future park while at the same time allowing for mineral extraction. The proper planning and coordination with GRG could save the Ottawa County Parks and Recreation Commission substantial money and resources in reshaping this area for the creation of the Bend Area Park.

This report update details current conditions of the site (soil borings). It focuses on the DeWent / GRG and OCRC portions of the site. The DeWent / GRG operations are winding down and intentions are to exit and dismantle the operation center when finished. This area is where the more significant park components are proposed to be developed. The report includes an estimated time frame for completion of mining operations and also determines the approximate value of the reclamation. The reclamation program also provides multiple, phased development concepts for a county park in various scenarios based upon the information that has been provided to date. The reclamation program includes guidelines for reclaiming shorelines, placing topsoil and overburden, shaping sub grades for future wetlands and shaping the remaining land and slopes for future park development areas based upon the acquired property.

Existing Conditions

To evaluate the existing conditions of the mining site, BFR examined portions of the site where mining operations have been reported as complete. Chapter 26 of the Georgetown Township ordinance has provisions requiring completed mine sites to have a 3:1 slope on all excavations angling to a body of water, 5:1 slopes for the first 25' underneath the body of water and 4 inches of topsoil spread across the entire site and seeded to establish vegetation for erosion control. BFR performed depth probes (July 2009) in the east lake where mine reclamation activities were supposed to have been completed. This was done by taking depth readings 25' away from the shoreline and calculating the corresponding slope to determine if the 5:1 ordinance requirement was met. It was discovered that multiple areas of reclaimed slope were not in compliance with this ordinance nor was there 4 inches of topsoil across the site and no evidence that seed had been spread to establish vegetation on the bare soils.

BFR is concerned about these conditions especially the slopes' erosion potential due to their steepness and lack of vegetation cover, particularly on the windward side. Another concern regards safety issues related to the development potential of public trails along these shorelines if the park plan is realized. These issues need to be resolved prior to the county taking ownership of this property.

Following the visit to the Bend Area mine sites to evaluate the existing conditions, BFR developed a revised plan for the proposed county park components. It is imperative to update the 2000 master plan because much of the site has changed

due to the location of deposits, spoil site expansion and additional deposit information. The updated plan reviews the new conditions and takes them into consideration relative to reconfiguring components with the future park plan in mind.

Inventory and Analysis

To begin, an updated inventory and analysis of the site was performed. A geotechnical report was commissioned to determine the conditions of the subsoils and also the characteristics of the mineral deposit. This information was used to make general decisions regarding future building sites and road locations. It also defined areas that could continue to be mined with the potential of creating a wetland and habitat area.

Design Development

BFR developed two reclamation scenarios to demonstrate the differences between a “standard reclamation plan” (p. 9-13) and the “proposed park reclamation plan” (p. 14-21).

Standard Reclamation Plan

The Standard Reclamation Plan shows the work that needs to be performed to generate a standard reclaimed site according to Chapter 26 of the Georgetown Township Zoning Ordinance.

The Areas of Non-Compliance (p. 9) shows the existing reclaimed areas not in compliance with the Township’s Zoning Ordinance. These areas will need to be addressed before mining operations cease. The Rough Grading Plan (p. 10) illustrates full excavation of all mineral deposits according to the Township Ordinance without incorporating any park elements or customized land shaping. Based on the anticipated depth of the excavated deposit under the standard reclamation plan, the seasonal fluctuations of the flood plain will cause this excavation to be partially filled with water; and, partially to completely dry during parts of the year. The depth of the water in this new excavation will be dependent on seasonal precipitation and respective flood conditions. The associated grading quantities and costs were calculated for the standard reclamation plan (p. 11) as well as topsoil and seeding quantities (p. 12). The Phasing Plan (p. 13) attempts to forecast future mining and reclamation activities for the site under this plan.

Park Development Reclamation Plan

A revised Park Master Plan was developed reflecting the existing conditions and current mining operations (p. 14) The revised master plan for the park incorporates most of the original components such as: a beach, bath house, boat launch, wetland and habitat areas, earth dams, observation blinds, and portions of the Ottawa County Regional Trail system. The active mining process provides the opportunity to create variable slopes along the banks of the excavation improving access to the wetland and habitat areas and also creating interesting topography for hiking along the wetland (p.16-17). The Park Master Plan also incorporates earth dams at the intersections of the wetland areas and the main lake to control water levels in these future wetland areas (p. 14). The Rough Grading Plan illustrates the excavation activities needed to

carry out these activities (p. 15). The associated quantities and costs for grading, topsoil and seeding in order to reclaim the site for park use were calculated and illustrated (p. 18-19). The Phasing Plan (p. 20) attempts to forecast future mining and reclamation activities for the site under this plan. In order to carry out these all of these phases, however, land acquisitions will need to take place. The Land Acquisition Map (p. 21) anticipates these acquisitions in the order shown.

The updated park plan provides multiple development options based upon different land acquisition possibilities. In concepts 1-3 we assume the acquisition of the GRG and DeWent properties by the Ottawa County Parks and Recreation Commission as envisioned in the 2000 plan. Discussions with the Ottawa County Road Commission have given the impression that it will be many years before the OCRC is willing to part with their land due to the size of the deposit and the relatively small extractions needed by the road commission and therefore OCPRC is reacting to that realization with these scenarios.

Concept 1 - shows a potential park layout if the Ottawa County Road Commission does not agree to use the majority of their land as part of the proposed park master plan in a timely fashion or not at all (p. 22). A small access easement is proposed by OCPRC to gain entry to the park site from the existing entry point off the east end of Fillmore Street. The road network extends across the entire southern edge of GRG land to access the Ottawa County park land to the east where a small parking lot is proposed.

Concept 2 - is another option if Ottawa County Road Commission does not agree to use the majority of their land as part of the proposed park plan (p. 23). This plan also calls for OCPRC to acquire a small access easement for entry off of the east end of Fillmore Street. However, the road network only services the proposed beach area and does not continue to the park land currently owned by OCPRC to the east adjacent to 12th Avenue. This property would be accessible through separate walking trails, the regional trail system, and from the small parking lot proposed off of 12th Avenue.

Concept 3 - proposes a 200' easement along the north and east edges of the Ottawa County Road Commission property for the development of a road to service the OCPRC property (p. 24). The 200' easement is of a size to help mitigate the mining operations and buffer park uses. This plan also routes the Ottawa County Regional Trail through this area which provides ample space to construct a trail system and establish vegetation.

Estimated Cost Analysis

Since GRG will complete their mining operations within the next 2-3 years and because most of the recreation components of the park are planned for the area owned by DeWent / GRG and the OCRC, we focused much of our efforts within this area. The cost estimates for each of the reclamation plans were divided between the GRG property and the OCRC property respectively. The prices for these estimates come directly from the GRG, which appear to be considerably less when compared with our estimated prices. (p. 25)

Comparing the Standard Reclamation Plan estimates with the Park Development Reclamation Plan estimates, it would be approximately twice as expensive for both GRG and OCRC to reclaim the site as a county park than it would be for them to excavate the site to its full mining potential and then reclaimed according to the Township Ordinance.

Page 25 of this report compares these estimates with an estimate for the OCPRC to reclaim the site as a county park after the GRG and OCRC mine the site to its full potential and then reclaim it according to the Township Ordinance. The prices for the PCPRC reclaimed site estimate were derived our estimated prices and are higher than the prices received from GRG. This comparison shows a cost savings for the County if they are able to retain GRG to reclaim the site as a county park.

Conclusion


The development of the updated Bend Area Mining Site Master Plan was an effort to reflect changes relating to the mining operations and land ownership that has occurred over the past decade. The adoption of this end use plan by all land owners involved is another important step in moving forward in accomplishing the long-term goal of developing a cohesive county park. More land acquisitions are needed to implement this plan, especially the acquisition of the DeWent/Grand Rapids Gravel Company property due to their plans to complete mining activity and begin the exit strategy. This acquisition should be a high priority within the next year to realize the significant park components of this future park site.

The other high priority is mine reclamation of the site. It is important that all existing non-active areas of the mine site be reclaimed immediately to ensure proper erosion control. At a minimum, this should be done in accordance with the Georgetown Township Ordinance. It is recommended, however, that OCPRC enter into an agreement with GRG and OCRC to allow GRG to complete all reclamation activities according to this updated master plan for future park use. It is also recommended that OCPRC set desired grades according the updated master plan in order for GRG to begin these reclamation activities as soon as possible.

It is further concluded that the existing reclaimed areas of the mine site are not in compliance with the Georgetown Township Ordinance. This must be rectified immediately or consequences will be imposed upon GRG either during the final land sale or in another monetary form.

Analysis Maps

SLOPE ANALYSIS MAP



LEGEND

ABOVE WATER LINE

 DOES NOT MEET ORDINANCE OR 2000 PLAN (3:1)


BELOW WATER LINE

 DOES NOT MEET 2000 PLAN (3.5:1)

 DOES NOT MEET ORDINANCE (5:1)




NORTH





Standard Reclamation Plan
(Per Township Ordinance)



LEGEND

- Property Lines
- Slopes exceed Ordinance max.

Grading Quantities and Costs

Property Owner	Above NWL (cy)	Below NWL (cy)	Costs
Grand Rapids Gravel Company	8,527	5,968	\$25,323.30


Above NWL = \$1.50/cy
Below NWL = \$2.10/cy

Topsoil and Seeding Quantities and Costs

Property Owner	Topsoil @ 4" depth (cy)	Seeding (acres)	Costs
Grand Rapids Gravel Company	9,490	17	\$20,971.50

Topsoil = \$1.35/cy
Seeding = \$480.00/acre





LEGEND

- Property Lines
- Deep Water/Excavation
- Shallow Water/Wetland

12TH AVENUE

HUIZENGA

FILMORE ST.


DEWENT/ GRAND
RAPIDS GRAVEL


LEASED FROM O.C.R.C.
TO G.R.G.C.

O.C.P.R.C.

COTTONWOOD AVE.

O.C.R.C.





LEGEND


- Property Lines
- Grading Above Normal Water Line
- Grading Below Normal Water Line


Grading Quantities and Costs

Property Owner	Above NWL (cy)	Below NWL (cy)	Costs
Grand Rapids Gravel Company	4,819	3,430	\$14,430.00
Ottawa County Road Commission	20,471	7,211	\$45,849.00

Above NWL = \$1.50/cy
Below NWL = \$2.10/cy

12TH AVENUE





LEGEND


- Property Lines
- Grand Rapids Gravel Company Topsoil and Seeding Area
- Ottawa County Road Commission Topsoil and Seeding Area


Topsoil and Seeding Quantities and Costs

Property Owner	Topsoil @ 4" depth (cy)	Seeding (acres)	Costs
Grand Rapids Gravel Company	17,628	33	\$39,638.00
Ottawa County Road Commission	24,457	46	\$55,097.00


Topsoil = \$1.35/cy
Seeding = \$480.00/acre


12TH AVENUE





LEGEND

-  Property Lines
-  PHASE 1 - FIX NON-COMPLIANCE RECLAMATION
-  PHASE 2 - MINE EXCAVATION
-  PHASE 3 - SHORELINE RECLAMATION
-  PHASE 4 - MINE EXCAVATION
-  PHASE 5 - MINE EXCAVATION
-  PHASE 6 - SHORELINE RECLAMATION
-  PHASE 7 - UPLAND RECLAMATION
-  PHASE 8 - UPLAND RECLAMATION



Park Development Reclamation Plan



LEGEND

- Ottawa County Trail Connection
- Interior Trail System
- ... Blue Trail Routes
- Wetland
- Core Wetland Habitat
- Open Water
- Interpretive Center
- Picnic Areas
- Active Recreation Area
- Beach Area/Amenities
- Vehicular Circulation
- ★ Wildlife Observation Platforms
- Trail Crossing

FILMORE ST.

COTTONWOOD AVE.


12TH AVENUE


Wetland Cut - 262,000 CY
Stockpile Capacity - 450,000 CY

Bottom of Stockpile
+620

Wetland Cut Level
+645

Stockpile Capacity
+670





LEGEND

- Wetland
- Core Wetland Habitat
- Open Water

FILMORE ST

COTTONWOOD AVE.


12TH AVENUE

Bottom of Stockpile
+620




Wetland Cut Level
+645


Stockpile Capacity
+670

Wetland Cut - 262,000 CY
Stockpile Capacity - 450,000 CY




RECLAIMED SLOPE SECTIONS





PICNIC SHELTER SITE PLAN DETAILS





LEGEND


- Property Lines
- - - Blue Trail Dredging
- Grading Above Normal Water Line
- Grading Below Normal Water Line


Grading Quantities and Costs

Property Owner	Above NWL (cy)	Below NWL (cy)	Costs
Grand Rapids Gravel Company	32,167	5,751	\$60,327.00
Ottawa County Road Commission	31,592	30,880	\$112,236.00

Above NWL = \$1.50/cy
Below NWL = \$2.10/cy

Ottawa County Road Commission
"Blue Trail" Dredging Costs - \$37,068 (\$6.00 CY)






LEGEND


-  Property Lines
-  Grand Rapids Gravel Company Topsoil and Seeding Area
-  Ottawa County Road Commission Topsoil and Seeding Area

Topsoil and Seeding Quantities and Costs

Property Owner	Topsoil @ 4" depth (cy)	Seeding (acres)	Costs
Grand Rapids Gravel Company	25,686	48	\$57,716.00
Ottawa County Road Commission	26,784	50	\$60,158.00

Topsoil = \$1.35/cy
Seeding = \$480.00/acre






LEGEND

-  Property Lines
-  PHASE 1 - FIX NON-COMPLIANCE RECLAMATION
-  PHASE 2 - MINE EXCAVATION
-  PHASE 3 - SHORELINE RECLAMATION
-  PHASE 4 - BEACH GRADING AND SHAPING
-  PHASE 5 - UPLAND RECLAMATION FOR BEACH DEVELOPMENT
-  PHASE 6 - UPLAND RECLAMATION FOR ACTIVE RECREATION
-  PHASE 7 - WETLAND DEVELOPMENT
-  PHASE 8 - UPLAND RECLAMATION
-  PHASE 9 - MINE EXCAVATION AND WETLAND DEVELOPMENT
-  PHASE 10 - SHORELINE RECLAMATION
-  PHASE 11 - UPLAND RECLAMATION

12TH AVENUE






LEGEND

- Property Lines
- Phase 1 - O.C.P.R.C.
- Phase 2 - Dewent/G.R.G.
- Phase 3 - O.C.R.C.
- Phase 4 - Huizenga

12TH AVENUE



Alternate Development Options




LEGEND


- Ottawa County Trail Connection
- Interior Trail System
- Blue Trail Routes
- Property Lines
- Wetland
- Open Water
- Picnic Areas
- Active Recreation Area
- Beach Area/Amenities
- Vehicular Circulation
- Proposed Access Easement
- Wildlife Observation Platforms
- Trail Crossing

FILMORE ST.

COTTONWOOD AVE.

12TH AVENUE






LEGEND

- Ottawa County Trail Connection
- Interior Trail System
- Blue Trail Routes
- Property Lines
- Wetland
- Open Water
- Picnic Areas
- Active Recreation Area
- Beach Area/Amenities
- Vehicular Circulation
- ★ Proposed Access Easement
- ★ Wildlife Observation Platforms
- Trail Crossing

FILMORE ST.

COTTONWOOD AVE.

12TH AVENUE






LEGEND

- Ottawa County Trail Connection
- Interior Trail System
- Blue Trail Routes
- Property Lines
- Wetland
- Open Water
- Picnic Areas
- Active Recreation Area
- Beach Area/Amenities
- Vehicular Circulation
- Proposed Access Easement
- Wildlife Observation Platforms
- Trail Crossing

FILMORE ST.

12TH AVENUE

COTTONWOOD AVE.



Standard Reclamation Plan

GRG Prices:

Grading Quantities and Costs

Property Owner	Above NWL (cy)	Below NWL (cy)	Costs
Grand Rapids Gravel Company	4,819	3,430	\$14,430.00
Ottawa County Road Commission	20,471	7,211	\$45,849.00

Above NWL = \$1.50/cy
Below NWL = \$2.10/cy

Topsoil and Seeding Quantities and Costs

Property Owner	Topsoil @ 4" depth (cy)	Seeding (acres)	Costs
Grand Rapids Gravel Company	17,628	33	\$39,638.00
Ottawa County Road Commission	24,457	46	\$55,097.00

Topsoil = \$1.35/cy
Seeding = \$480.00/acre

BFR Estimated Prices:

Grading Quantities and Costs

Property Owner	Above NWL (cy)	Below NWL (cy)	Costs
Grand Rapids Gravel Company	4,819	3,430	\$18,560.25
Ottawa County Road Commission	20,471	7,211	\$62,284.50

Above NWL = \$2.25/cy
Below NWL = \$2.25/cy

Topsoil and Seeding Quantities and Costs

Property Owner	Topsoil @ 4" depth (cy)	Seeding (acres)	Costs
Grand Rapids Gravel Company	17,628	33	\$64,413.00
Ottawa County Road Commission	24,457	46	\$89,528.25

Topsoil = \$2.25/cy
Seeding = \$750.00/acre

Park Reclamation Plan

GRG Prices:

Grading Quantities and Costs

Property Owner	Above NWL (cy)	Below NWL (cy)	Costs
Grand Rapids Gravel Company	32,167	5,751	\$60,327.00
Ottawa County Road Commission	31,592	30,880	\$112,236.00

Above NWL = \$1.50/cy
Below NWL = \$2.10/cy

Topsoil and Seeding Quantities and Costs

Property Owner	Topsoil @ 4" depth (cy)	Seeding (acres)	Costs
Grand Rapids Gravel Company	25,686	48	\$57,716.00
Ottawa County Road Commission	26,784	50	\$60,158.00

Topsoil = \$1.35/cy
Seeding = \$480.00/acre

BFR Estimated Prices:

Grading Quantities and Costs


Property Owner	Above NWL (cy)	Below NWL (cy)	Costs
Grand Rapids Gravel Company	32,167	5,751	\$85,315.50
Ottawa County Road Commission	31,592	30,880	\$140,562.00

Above NWL = \$2.25/cy
Below NWL = \$2.25/cy

Topsoil and Seeding Quantities and Costs

Property Owner	Topsoil @ 4" depth (cy)	Seeding (acres)	Costs
Grand Rapids Gravel Company	25,686	48	\$93,793.50
Ottawa County Road Commission	26,784	50	\$97,764.00

Topsoil = \$2.25/cy
Seeding = \$750.00/acre




Bend Area - Potential Acquisitions




Huizenga Property





SITE DEVELOPMENT PLAN CONCEPT
BEND AREA
 GRAND RIVER GREENWAY - GEORGETOWN TOWNSHIP





Ottawa County Parks & Recreation Commission
 12220 Fillmore St. West Olive, MI 49460
 (616) 738-4810 www.mioottawa.org/parks

REQUEST –

(ML2002) Renewal of (ML1502) Ottawa County Road Commission -1551 Taylor St. (August 6, 2020)

The request is for a renewal of an existing mining license which, as per previous minutes, used excavated materials for road maintenance purposes only, not for profit. Note that this license is for the Ottawa County Road Commission, which is the same entity (Ottawa County) as the Ottawa County Parks, which is coordinating the reclamation of the land into the Bend in the River County Park.

MAPS





Ottawa County Road Commission
14110 Lakeshore Drive
Grand Haven, Michigan 49417
(616) 842-5400
info@ottawacorc.com

July 9, 2020

Mannette Minier
Georgetown Township
1515 Baldwin Street
P.O. Box 769
Jenison, Michigan 49429

Re: OCRC Pit Properties
Parcels: 70-14-02-300-05 and 009 and 010; 70-14-03-400-027 and 028

Mannette,

The Ottawa County Road Commission (OCRC) has 97.7 acres within 5 parcels of land in Sections 2 and 3 of Georgetown Township (see attached map) that make up the pit known as the "Cheyne Pit". Since 1979, Grand Rapids Gravel has leased parcels 70-14-03-400-028 and 70-14-02-300-009 of our pit property for staging and processing areas as they mined parcels of land to the north and east. The remaining parcels have been mined by our staff at low rate with the removal of a few hundred yards of bank run material per year.

With the anticipation that Grand Rapids Gravel will be completing their operations in the next few years, OCRC will start the process to evaluate all 5 parcels to determine the amount and locations of the natural aggregate resources. OCRC has discussed the potential to expand the Bend Area Open Space with Ottawa County Parks & Recreation as previously indicated in the Master Plan for the area, and there is still a mutual interest to expand and establish a park on most of our 97.7 acres of property.

Once the evaluation of our pit property is complete, OCRC intends to continue the discussions with Ottawa County Parks & Recreation to develop a reclamation plan that will maximize the removal of natural aggregate to align with a potential layout for the Bend Area Open Space. The OCRC will be able to provide more specific information about the limits, acreage, and depth of the mining operation, once the all the appropriate exploratory borings have been obtained and a consultant has been retained to develop site plans for permitting and discussions.

Please let me know if you have any questions or require additional information.

Sincerely,

A handwritten signature in black ink, appearing to read "Brett A. Laughlin", with a long horizontal flourish extending to the right.

Brett A. Laughlin, P.E.
Managing Director

HISTORY – Brief Summary

Temporary licenses were issued for ML9901, ML9902, ML9903 and ML9904 on 9-7-99. The condition for approval at that time was that permanent licenses would be issued at the time that the company accepts the Bend in the River Plan as the reclamation plan or presents an alternative reclamation plan.

The following are the dates that the companies accepted the Bend in the River Plan and the permanent licenses were issued as per the Mining Board:

Huizinga Gravel – 6/21/2001

Mining licenses - (ML9902), (ML0504), (ML1006), ML1504

Ottawa County Road Commission – 5/10/2001

Mining licenses - (ML9903), (ML0505), (ML1001), ML1502

Boynton Gravel – 5/10/2001

Mining licenses - (ML9904), (ML0503), (ML1005), ML1503 (now closed, reclaimed and possession given to the Ottawa County Parks Department.

Grand Rapids Gravel/DeWent – 1/31/2001

Mining licenses - (ML0101), (ML0502), (ML1004), ML1501, now ML1902

The minutes of September 7, 1999 indicate that the mining would continue for possibly ten years, which would have been 2009.

TOWNSHIP GOAL

The Township recognizes that the materials that are mined are a valuable resource and this is important to the community and area. In this instance, the materials are used in the maintenance of roads. The goal is to have excavation completed as soon as possible and to have the land restored as per the restoration plan consistently approved with the initial mining license and with each subsequent renewal, which is the Bend in the River Plan for a County Park.


How to accomplish the goal.

1. The most important objective is to prohibit bringing additional materials onto the site and to prohibit a crushing operation which in itself is an operation where materials are brought onto the site.
2. The way to begin to accomplish the goal is for the land where excavation is completed to be restored as per the Bend in the River Plan. It would be the land owner's decision as to whether the owner wants to restore the land as per the Bend in the River Plan or to have Ottawa County restore the land as per the plan.
3. The Bond or LOC would be used by the Township to complete the restoration if it wasn't completed by the drop dead end date.
4. The Bond or LOC could continuously be decreased as land is actually restored as per the Bend in the River Plan.
5. The property owner could either restore the land as per the Bend in the River Plan or have Ottawa County restore the land.

SUMMARY

The following pertains to the Ottawa County Road Commission mining operation:

1. As per the applicant, the Ottawa County Road Commission only removes a few hundred yards of bank run per year.
2. The operation includes:
 - a. P.P. # 70-14-03-400-027, 28.88 acres;
 - b. P.P. # 70-14-02-300-009, 21.81 acres;
 - c. P.P. # 70-14-03-400-028, 6.84 acres;
 - d. P.P. # 70-14-02-300-010, 20.31 acres;
 - e. P.P. # 70-14-02-300-005, 19.89 acres.
3. Grand Rapids Gravel leases P.P. 70-14-02-300-009, 21.81 acres, and P.P. # 70-14-03-400-028, 6,84 acres, from the OCRC. See below.



4. With the approval of the renewal/new mining license for Grand Rapids Gravel (ML1902) the timeline for the completion of the GRG operation is as follows, which pertains to the Ottawa County Road Commission land leased by GRG:

- a. From January 1, 2022 to December 31, 2022, GRG will:
 - i. Remove all stockpiled material that has been processed and remains on property on the Site that is leased from the Ottawa County Road Commission (P.P. #70-14-03-400-028 and 70-14-02-300-009);
 - ii. Break down and remove the processing plant located on said leased property; and
 - iii. Remove concrete under the processing plant and crush said concrete onsite in lieu of hauling all broken material offsite.
- b. By December 31, 2022, GRG commits to having all stockpiles removed, and the processing plant removed from the leased property (with the exception of material left solely for use by Ottawa County at the Site).
- c. During the period of January 1, 2023 and June 30, 2023, GRG will reclaim the leased property; and
- d. After the earlier of completion of the reclamation of the leased property or June 30, 2023, GRG will conclude all activities related to ML1902 on all seven parcels.

DISCUSSION POINTS

- The mining ordinance was adopted in 1998 with the goal and intent that minerals could be extracted from a site and when that was completed, the land was to be restored. This goal was even stated as far back as the 1964 Zoning Ordinance.
- Georgetown Township wants the excavating to be completed in the Township and the land to be reclaimed and restored.

DETERMINATIONS

The Mining Board is charged with determining the following:

1. Although the ordinance requires a performance bond, the Ottawa County Road Commission and the Ottawa County Parks and Recreation both are under the authority of the Ottawa County Board of Commissioners, which provides leadership and policy direction for all County activities. Requiring a performance bond from the County to ensure that the County restores and reclaims the land for the County Park is not necessary, as per the Ottawa County Parks Director. However, the Mining Board can make that decision. If the determination is that one is needed, it should be related to the acreage remaining to be mined and restored. The site is 97.7 acres, less 28.65 leased by GRG, is 69.05 acres left. Based on the escrow amount of \$1,000 per acre remaining to be mined and restore (how much has already been restored), the performance bond should be _____. Note that the County may appear before the Board to request a pro-rata reduction in the amount of the performance guarantee for each acre restored and reclaimed.
2. The timeline for completion should be determined. An option would be to approve the renewal of the mining license until June 30, 2023 because that is the date when Grand Rapids Gravel is required to have mining completed and the land leased from Ottawa County Road Commission restored. If the license was required to be renewed by June 30, 2023, the County could provide more accurate information as to what land remains to be mined and to draft a timeline for completion.

OPTION FOR MOTION

Motion: Insofar as the Township recognizes that the materials that are mined are a natural and valuable resource and this is important to the community and area, the Mining Board grants approval of (ML2002) which is the renewal of (ML1502) Ottawa County Road Commission -1551 Taylor St., and to incorporate the findings and conclusions in the Staff Report dated August 6, 2020, with the following conditions:

- The license shall expire **June 30, 2023 when Grand Rapids Gravel has vacated the Ottawa County Road Commission property**, unless suspended or revoked earlier per the Ordinance. At that time the operator shall return with a more detailed plan, including areas remaining to be excavated and a timeframe for completion of the excavating of materials from the site.
- **A performance bond, as required in Sec. 26.81 of the Mining Ordinance, in the form of an amount is to be paid to the Township relative to the acres of land remaining to be reclaimed or restored. The amount for the escrow per acre remaining to be restored or reclaimed is _____ (if any), as determined by the Mining Board. This amount shall be paid no later than September 15, 2020 in order for the mining license to remain in effect. Technically the bond should have been paid prior to the expiration of the mining license on June 30, 2020. The amount of the escrow may be periodically reduced upon request by the mining company, proportionate to the number of acres that are reclamation or restoration.**
- The Site shall be operated in compliance with all previous approvals and the conditions of approval.
- The operator shall comply with all federal, state, and local laws, regulations and ordinances.
- All terms and conditions as presented with the initial application materials remain in effect;
- Hours of operation be limited to 7:00 a.m. to 6:00 p.m. Monday to Friday, 8:00 a.m. to 3:00 p.m. Saturday, and no Sundays or holidays;
- The haul route shall continue as approved with the previous approvals. All roads within the site are to be maintained in a manner that controls dust and prevents debris from being carried onto public streets;
- If any berms are created, they are to be maintained;
- No future reclamation approvals are implied by the approval of this reclamation plan and the applicant must obtain approval as required by all other Township ordinances;
- Approval from the Ottawa County Road Commission must remain in effect;
- All entrances and exits to the site shall be securely locked during hours when mining operations are not permitted on the site.
- All vehicles used to transport excavated material shall be loaded in a manner so that the material cannot be unintentionally discharged from the vehicle. Vehicles shall be cleaned of all material not in the load-bed prior to entering the public streets. If materials excavated from the site are deposited or spilled upon the public roadway, it shall be the responsibility of the licensee, without requiring any action or request by the township, to immediately remove the spilled or deposited material;
- A licensee shall comply with all soil erosion, wetlands and floodplain rules and regulations of the State of Michigan, Ottawa County and the township;
- Fueling of vehicles on any site shall comply with statutes, rules and regulations enforced and implemented by the Michigan Department of Environmental Quality;
- All roads within the site are to be maintained in a manner that controls dust and prevents debris from being carried onto public streets.

- If filling of an excavated area is necessary during reclamation, only inert material, as defined by the Michigan Solid Waste Management Act (Act No. 641 of the Public Acts of 1978, as amended) shall be used.
- Upon termination of mining operations, the licensee shall be responsible to reclaim the site in accordance with reclamation plans approved by the review board, **which is the Bend in the River Plan**. If the licensee fails to reclaim the site as required by the approved reclamation plans, the township may come upon the site and reclaim the land in accordance with those plans and may use the proceeds of the performance guarantee (if any) required by this article to defray the costs of the reclamation.
- Upon the cessation of all mining operations (or any phase of operations, as applicable) except stockpiling, and within a reasonable period of time, not exceeding 12 months thereafter, all tanks, buildings, stockpiles, and equipment shall be removed from the site unless the building or structures can lawfully be used on the site for other purposes as permitted by applicable laws or ordinances.
- Storage and stockpiling of mined products after cessation of mining activities may be permitted by the review board by annual license granted for that limited purpose. In no event shall any additional materials be allowed to be added to these stockpiles and a license granted for storage or stockpiling of mined products shall not interfere with or excuse reclamation as otherwise required under this article.
- **In no event shall any additional materials be allowed to be brought onto the site or added to any stockpiles.**
- **The license does not include a crushing operation.**
- No additional materials are required of the applicant at this time since the initial application contained all the required submittal materials and nothing has changed as of this time. In addition, a site inspection was conducted and the site is in conformance with the terms of the initial mining license as well as other Township ordinances;
- And with the condition that the operation on the site continues to work towards the Bend in the River Reclamation Plan.

REQUEST – (August 6, 2020)


(ML2003) Renewal of (ML1504) Huizinga Gravel. The request is for a renewal of an existing mining license for the excavation of materials located on the Huizinga Gravel mining site and processing of those materials. **No request was made to bring additional materials onto the site for processing and no request was made for a crushing operation. Currently neither exist on the site.**

The Huizinga property includes the following:

1. Western- most parcel - 9449 22nd Ave., P.P. # 70-14-03-100-017; 77.77 acres. **This is completed and restored with slopes as per the mining ordinance. This is not part of the Bend in the River Plan except for the proposed trail to go along the northern portion, and south along the western property line, to connect to 22nd Ave./Begole.** The future plan is to develop it as single family homes. This parcel was shown as completed on the site plan dated July 20, 1999, for the initial application because the mining was completed prior to the adoption of the Mining Ordinance in 1998.
2. One of two eastern parcels - 1949 Fillmore St., P.P. # 70-14-03-200-001; 40.59 acres. **Mining is currently taking place and planned for the future. This is part of the Bend in the River Plan.**
3. One of two eastern parcels - 1861 Fillmore St., P.P. # 70-14-03-200-002; 58.87 acres. **Mining is currently taking place and planned for the future. This is part of the Bend in the River Plan.**
4. Northern parcel along the Grand River - Begole St., P.P. # 70-10-34-400-026 , 17.71 acres. **No mining is taking place or is planned for the future on this parcel. It is wooded and the plan is to leave it as it is, which is what the County wants. This is part of Bend in the River Plan.**
5. The total of all the property is 194.95 acres. After subtracting the completed parcel and the wooded parcel to the north, **99.46 remain where mining is currently occurring and will in the future.**

The operator has indicated the mining (excavation) will be completed in ten years.

MAPS



HISTORY – Brief Summary

The following are the dates that the companies accepted the Bend in the River Plan and the permanent licenses were issued as per the Mining Board:

Huizinga Gravel – 6/21/2001

Mining licenses - (ML9902), (ML0504), (ML1006), ML1504

Ottawa County Road Commission – 5/10/2001

Mining licenses - (ML9903), (ML0505), (ML1001), ML1502

Boynton Gravel – 5/10/2001

Mining licenses - (ML9904), (ML0503), (ML1005), ML1503 (now closed, reclaimed and possession given to the Ottawa County Parks Department.

Grand Rapids Gravel/DeWent – 1/31/2001

Mining licenses - (ML0101), (ML0502), (ML1004), ML1501, now ML1902

TOWNSHIP GOAL

The Township recognizes that the materials that are mined/excavated are a valuable resource which are important to the community and area. The goal is to have excavation completed as soon as possible and to have the land restored as per the restoration plan consistently approved with the initial mining license and with each subsequent renewal, which is the County Bend in the River Park. However, the Township recognizes that the mining companies have the right to excavate all of the materials on the site.

How to accomplish the goal.

1. The most important objective is to prohibit the operator from bringing additional materials onto the site and to prohibit a crushing operation which in itself is an operation where materials are brought onto the site.
2. The way to begin to accomplish the goal is for the land where excavation is completed to be restored as per the Bend in the River Plan. This would take place in conjunction with Ottawa County.
3. The Bond or LOC (Letter of Credit) would be used by the Township to complete the restoration if it wasn't completed by the drop dead end date.
4. The Bond or LOC could continuously be decreased as land is actually restored as per the Bend in the River Plan.
5. The property owner could either restore the land as per the Bend in the River Plan or have Ottawa County restore the land.

SUMMARY

The following pertains to the Huizinga mining operation:


1. Huizinga Gravel has already sold a piece of property to the Ottawa County Parks.
2. The operation includes:
 - a. As per the site plan dated 7/2/20, active mining and processing is currently taking place on P.P. # 70-14-03-200-001 and P.P. # 70-14-03-200-002. The plan also shows future mining on these two sites and relocation of the processing area for the future mining phase. These two parcels have a total of 99.46 acres and are a part of the Bend in the River Plan.
 - b. No mining is currently taking place on P.P. # 70-14-03-100-017 (77.77 acres) because mining is completed and the land is restored with slopes that meet ordinance requirements. This land has not been a part of the mining license beginning with the initial one because mining occurred and was completed prior to the adoption of the Mining Ordinance in 1998.
 - c. No mining is currently taking place on P.P. # 70-10-34-400-026 (17.72 acres) and no future mining is indicated for it because it is to be left as wooded.
3. Ottawa County Parks plan for acquisitions shows that only part of the Huizinga property will be acquired.



Bend Area - Potential Acquisitions



Ottawa County Parks & Recreation
1 inch = 1,000 feet



Huizinga Property

4. Consequently, Huizinga Gravel should provide a reclamation plan for the property not proposed to be acquired by Ottawa County Parks for the Bend in the River Park. It may be pre-mature to require a reclamation plan at this point because the above maps are merely proposals that could be altered with the passage of time. **An option would be to require that the reclamation plan be submitted for the area not to be acquired by Ottawa County at the time Huizinga Gravel applies for a license renewal in 2025.**

DETERMINATIONS NEEDED

The Mining Board is charged with determining the following:

1. The performance bond is related to the acreage remaining to be mined and restored. The total acreage of the two parcels where mining is taking place and will in the future is 99.46. As per a conversation with Ottawa County Parks, about one-third of this acreage will be or is open water, with no restoration needed. Therefore, the performance bond should be charged for about 60 to 70 acres and would be between \$60,000 and \$70,000 based on the previous amount of \$1,000 per acre remaining to be mined and restore that was charged to Grand Rapids Gravel. The Mining Board could determine an amount or have the mining operator present a document detailing exactly how many acres remain to be restored. Note that Huizinga Gravel may appear before the Board to request a pro-rata reduction in the amount of the performance guarantee for each acre restored and reclaimed. What amount should the performance bond be?
2. The timeline given by Huizinga Gravel to complete the mining (excavation) is ten years. Therefore, should the license be renewed until June 30, 2025?
3. Should the additional reclamation plan be required to be submitted prior to expiration of this license in 2025?

OPTION FOR MOTION

Motion: Insofar as the Township recognizes that the materials that are mined are a natural and valuable resource and this is important to the community and area, the Mining Board grants approval of (ML2003) which is the renewal of (ML1504) Huizinga Gravel, as shown on the site plan dated 7/2/20, and to incorporate the findings and conclusions in the Staff Report dated August 6, 2020, with the following conditions:

- The license shall expire _____ (**June 30, 2025? Maximum time**), unless suspended or revoked earlier per the Ordinance. At that time of renewal of this license (ML2003) in 2025, a reclamation plan shall be submitted for the property that will not be included in the Bend in the River Park Plan. A firm date of completion shall also be provided.
- **A performance bond, as required in Sec. 26.81 of the Mining Ordinance, is to be paid to the Township relative to the acres of land remaining to be reclaimed or restored. The amount based on \$1,000 per acre remaining to be restored or reclaimed is _____, as determined by the Mining Board. This amount shall be submitted to the Township no later than September 15, 2020 in order for the mining license to remain in effect. Technically the bond should have been paid prior to the expiration of the mining license on June 30, 2020. The amount of the guarantee may be periodically reduced upon request by the mining company, proportionate to the number of acres that are reclamation or restoration.**
- The Site shall be operated in compliance with all previous approvals, including the conditions of approval.
- All terms and conditions as presented with the initial application materials remain in effect
- The operator shall comply with all federal, state, and local laws, regulations and ordinances.
- Hours of operation be limited to 7:00 a.m. to 6:00 p.m. Monday to Friday, 8:00 a.m. to 3:00 p.m. Saturday, and no Sundays or holidays.
- The haul route shall continue as approved with the previous approvals. All roads within the site are to be maintained in a manner that controls dust and prevents debris from being carried onto public streets.
- If any berms are created, they are to be maintained.
- No future reclamation approvals are implied by the approval of this reclamation plan and the applicant must obtain approval as required by all other Township ordinances.
- Approval from the Ottawa County Road Commission must remain in effect.
- All entrances and exits to the site shall be securely locked during hours when mining operations are not permitted on the site.
- All vehicles used to transport excavated material shall be loaded in a manner so that the material cannot be unintentionally discharged from the vehicle. Vehicles shall be cleaned of all material not in the load-bed prior to entering the public streets. If materials excavated from the site are deposited or spilled upon the public roadway, it shall be the responsibility of the licensee, without requiring any action or request by the township, to immediately remove the spilled or deposited material.
- A licensee shall comply with all soil erosion, wetlands and floodplain rules and regulations of the State of Michigan, Ottawa County and the township.
- Fueling of vehicles on any site shall comply with statutes, rules and regulations enforced and implemented by the Michigan Department of Environmental Quality.
- All roads within the site are to be maintained in a manner that controls dust and prevents debris from being carried onto public streets.

- If filling of an excavated area is necessary during reclamation, only inert material, as defined by the Michigan Solid Waste Management Act (Act No. 641 of the Public Acts of 1978, as amended) shall be used.
- Upon termination of mining operations, the licensee shall be responsible to reclaim the site in accordance with reclamation plans approved by the review board, **which is the Bend in the River Plan and the plan to be submitted for the next approval of renewal for the property not included in the Bend in the River Plan.** If the licensee fails to reclaim the site as required by the approved reclamation plans, the township may come upon the site and reclaim the land in accordance with those plans and may use the proceeds of the performance guarantee required by this article to defray the costs of the reclamation.
- Upon the cessation of all mining operations (or any phase of operations, as applicable) except stockpiling, and within a reasonable period of time, not exceeding 12 months thereafter, all tanks, buildings, stockpiles, and equipment shall be removed from the site unless the building or structures can lawfully be used on the site for other purposes as permitted by applicable laws or ordinances.
- Storage and stockpiling of mined products after cessation of mining activities may be permitted by the review board by annual license granted for that limited purpose. In no event shall any additional materials be allowed to be added to these stockpiles and a license granted for storage or stockpiling of mined products shall not interfere with or excuse reclamation as otherwise required under this article.
- **In no event shall any additional materials be allowed to be brought onto the site or added to any stockpiles.**
- **The license does not include a crushing operation.**
- No additional materials are required of the applicant at this time since the initial application contained all the required submittal materials and nothing has changed as of this time. In addition, a site inspection was conducted and the site is in conformance with the terms of the initial mining license as well as other Township ordinances;
- The operation on the site shall continue to work towards the Bend in the River Reclamation Plan.

Huizenga Mineral Mining Renewal Request

Response to June 11, 2020 letter from Georgetown Township
July 2, 2020

Below please find the responses to the items as requested in the June 11, 2020 letter. The italicized print are the items in the letter, our responses are in bold print.

1. *A site plan showing the following (could be one site plan of the entire area or could be individual site plans):*

- a. *The existing conditions on the site:*

The mineral mining plan submitted on March 20, 2020 was intended to illustrate the existing site conditions. Upon further review of the plan, the applicant has asked that some more information and detail be added to the plan. This plan (revision date 7/2/20) has been revised as follows:

- **Title block with address corrected & applicant name referenced (Huizenga Gravel).**
- **The possible future trail per the Ottawa County Parks & Recreation Commission (OCPRC) master plan has been modified just east of the existing processing area to more accurately reflect the location of the "land bridge" being constructed by Huizenga Gravel in coordination with the OCRPC.**
- **The existing processing area has been labelled future mining area as well. Once the mining is completed in all areas except this current processing area, the processing area will be relocated to the south side of the mining operation. The final phase of mining will then be able to be completed in the area of current processing operation.**
- **Limits of active and future mining areas have been clarified further on the revised plan. The majority of the active mining is taking place on parcel -200-002. In addition, the relocated haul road shown in yellow on parcel 200-001 along with the former haul road adjacent and to the east is also part of the active mining operation.**
- **General notes 6, 7, and 8, on the previously submitted plan have been removed. Huizenga Gravel only intends to process road gravel and no supplemental crushing operation is proposed. As part of Huizenga Gravel's coordination effort with the OCPRC to construct the land bridge to create the trail, some clay may be imported into the site to provide the necessary fill for this effort.**

- b. *The areas remaining to be excavated, along with the estimated amount of materials remaining to be excavated:*

A separate 11" x 17" phasing map is included in this latest submittal that shows the areas actively being mined, as well as future mining phases. An estimated amount of material left to mine is indicated on the map for each phase. The actual amount of material mined will be based on the quality and quantity of the material encountered. Based on the average sales of 105,000 cubic yards of material per year over the last number of years, the remaining material to be mined/sold would require about 10 years to complete.

- c. *The areas of the land that have been restored or reclaimed as per the reclamation plan or as per the provisions in the Township Mining Ordinance.*
- d. *The areas remaining to be restored or reclaimed:*

(Response for c & d)

Because the active mining area continues in the areas noted, no formal restoration of these areas has been undertaken. Huizenga Gravel is aware of the requirements of Georgetown Township Mining Ordinance for final restoration, and is committed to having the site brought into compliance following completion of the mining operation.

- 2. *A detailed timeframe for the completion of mining operations on the site, including when the land will be reclaimed or at least restored to the Township Mining Ordinance standards.*

The active mining areas shown on the plan indicate a 5-year window (2020-2025). Although Huizenga Gravel is committed and eager to complete the mining operation, it is difficult to predict the factors that impact the demand for this resource. The economy from 2008-2010, the unusual high-water levels experienced during the last few years, and most recently, COVID-19 are just 3 examples that are totally out of Huizenga Gravel's control that impact the completion date of the mining. Huizenga Gravel will continue to keep the Township informed of the operation. However, based on the material left to be mined, Huizenga Gravel is requesting another 10 year extension of their mining permit.

A reference in the 6/11/20 letter to the required performance bond per Georgetown Mining ordinance, Section 26.81 is acknowledged. Huizenga Gravel will propose an appropriate amount for the restoration effort along with the basis of the amount determined. This will be provided in the next couple of weeks for staff review prior to the August 19, 2020 Mineral Mining Board.

In response to the comment of Huizenga Gravel accepting the Bend in The River Plan of 2000 as their reclamation plan, Huizenga Gravel continues to communicate with the representative(s) of the OCPRC in implementing this plan. In fact, Huizenga Gravel sold a portion of property they owned along the river to OCPRC. They have also negotiated a right of first refusal with the OCPRC for additional property with river frontage. In addition, as previously referenced Huizenga Gravel is working with OCPRC to construct the possible trail through the property as shown on the plans submitted. Aside from these items, the Huizenga property does not encompass improvements planned per the Bend in the River Plan as illustrated clearly in the updated 2010 report by Bauer & Ford.

We are confident that with submittal of this supplemental information, the Georgetown Township Mining Board will have all the information needed to approve the mining permit extension. A representative from Huizenga Gravel will be attending the August 19, 2020 meeting and will be more than happy to answer any questions the Mining Board may have.



SOIL BORING DATA:

SOIL BORING NO. 1 0.0' - 3.0' FILL (CLAY) 3.0' - 10.0' GRAVEL 10.0' - 50.0' FINE SAND 50.0' - 55.0' WATER TABLE @ 6.0'	SOIL BORING NO. 4 0.0' - 1.0' TOPSOIL W/GRAVEL 1.0' - 6.0' GRAVEL W/CLAY 6.0' - 18.0' GRAVEL 18.0' - 32.0' MEDIUM-FINE SAND 32.0' - 50.0' FINE SAND, WATER TABLE @ 32.0'	SOIL BORING NO. 7 0.0' - 10.0' SAND AND GRAVEL 10.0' - 25.0' WATER TABLE @ 25.0' 25.0' - 45.0' FINE SAND, WATER TABLE @ 25.0'
SOIL BORING NO. 2 0.0' - 10.0' SAND AND GRAVEL 10.0' - 16.0' GRAVEL 16.0' - 18.0' CLAY 18.0' - 50.0' FINE SAND, WATER TABLE @ 10.0'	SOIL BORING NO. 5 0.0' - 1.0' TOPSOIL 1.0' - 2.5' CLAY AND GRAVEL 2.5' - 17.0' SAND AND GRAVEL 17.0' - 34.0' MEDIUM-FINE SAND 34.0' - 50.0' FINE SAND, WATER TABLE @ 34.0'	SOIL BORING NO. 8 0.0' - 15.0' SAND AND GRAVEL, WATER TABLE @ 25.0' 15.0' - 23.0' FINE SAND 23.0' - 25.0' CLAY
SOIL BORING NO. 3 0.0' - 1.0' TOPSOIL W/GRAVEL 1.0' - 4.0' GRAVEL W/CLAY 4.0' - 10.0' SAND AND GRAVEL 10.0' - 17.0' GRAVEL 17.0' - 27.0' MEDIUM-FINE SAND 27.0' - 50.0' FINE SAND, WATER TABLE @ 30.0'	SOIL BORING NO. 6 0.0' - 4.0' FINE SAND, MET 4.0' - 6.0' CLAY 6.0' - 25.0' FINE SAND, WATER TABLE @ 10.0' 25.0' - 35.0' CLAY	SOIL BORING NO. 8 0.0' - 17.0' SAND AND GRAVEL, WATER TABLE @ 5.0' 17.0' - 20.0' CLAY

- GENERAL NOTES**
- PROPERTY DESCRIPTION**
70-14-03-100-017
PART OF NW FRL 1/4 COM AT W 1/4 COR, TH E 1450.54 FT TO PT OF BEG, TH N 03D 19M 44S W 346 FT, E 33.06 FT, TH N 03D 19M 44S W 1355.78 FT ALG CEN LI OF 22ND AVE, TH NE'LY 73.55 FT ALG A 47 FT RAD CURVE TO LEFT (CHD BEARS N 48D 09M 32S W 66.27 FT), S 87D 0M 40S W 81.28 FT, TH N 03D 19M 44S W 949.35 FT ALG W LI OF E 1/2 OF NW FRL 1/4, TH S 89D 45M 36S E 1327.37 FT ALG N SEC LI TO N 1/4 COR, TH S 03D 55M 55S E 2687.31 FT ALG N&S 1/4 LI TO CEN 1/4 COR, TH W 1260.22 FT ALG E&W 1/4 LI TO BEG. SEC 3 T6N R13W 77.79 AC
 - MAPPING:**
 - Boundary information is based on available remonumentation and sectional information by Excel Engineering, Inc.
 - 2 foot interval existing ground contours and topographical features are based on aerial survey photography provided by existing Ottawa County G.I.S.
 - Existing utilities and adjacencies are based on available records.
 - This site is located within the 100 Year Flood Plain, based on the National Flood Insurance Program Rate Maps.
 - ZONING:** Existing classification is "RR"
District regulations:
Front setback = 40 ft.
Side yard = 20 ft.(40 ft. total)
Rear yard = 50 ft.
Lot area = 30,000 sq.ft.
Lot width = 200 ft.
 - EXISTING LAND USE:** Mineral Mining
 - PROPOSED IMPROVEMENTS:**
 - All sand mineral removal operations are subject to restrictions in the Georgetown Township Mineral Mining Ordinance beginning with Section 6(e)XVIII.
 - Traffic flow will be from the intersection of Fillmore Street and Cottonwood Drive to either the West or Southeast.
 - No additional buildings will be placed on the site. Existing buildings may be removed in the future. Current gravel processing equipment will be used and in the future will be moved to the SE corner of the property.
 - Where adjoining parcels are operating under existing gravel extraction permits, the gravel extraction limits will be the property lines. No cut or excavation will be made closer than 50' to any other property line.
 - That portion of gravel access roads within the area of operation will maintain dust control by a water truck on an as needed basis.
 - The completion of mining operation is anticipated to be 10 years with final reclamation to follow.
 - Additional materials may be allowed to be brought onto the site for processing of fill.
 - Mining license does include a crushing operation.
 - Wetland/Shallow water areas as identified on the Bend in the River Master Plan are exempt from the 5 foot minimum/10 foot average depth rule.

GENERAL NOTES:
1. PHOTO DATE = 2018

BENCHMARK ELEVATION: 599.95
CENTER OF SECTION REFERENCE POINT
SECTION 2, T6N, R13W GEORGETOWN TWP.



BEND IN THE RIVER MINING ENLARGED SITE PLAN - HUIZENGA

FOR: HUIZENGA LAND LLC
ATTN: MR. BILL HUIZENGA
10075 GORDON ST
PO BOX 258

IN: PART OF THE W 1/2, SECTION 2, T6N, R13W, GEORGETOWN TOWNSHIP, OTTAWA COUNTY, MICHIGAN

<p>excel engineering, inc. planners - engineers - surveyors 5252 Clyde Park, S.W. • Grand Rapids, MI 49509 Phone: (616) 531-3660 Fax: (616) 531-2121 www.excelengineering.com</p>		<p>SHEET 1 of 1</p>
<p>DRAWN BY: MK APPROVED BY: DDG FILE NO.: 911516E</p>	<p>PROJ. ENG.: DDG PROJ. SURV.: DATE: 03-19-10</p>	

P:\Projects\1910115\191011502\dwg\enlarged\115E_2019 Mining.dwg - HUIZENGA, 3/20/2020 2:28:29 PM, mmett



SOIL BORING DATA:

SOIL BORING NO. 1 0.0' - 3.0' FILL (CLAY) 3.0' - 10.0' GRAVEL 10.0' - 50.0' FINE SAND 50.0' - 55.0' CLAY WATER TABLE @ 6.0'	SOIL BORING NO. 2 0.0' - 10.0' SAND AND GRAVEL 10.0' - 16.0' GRAVEL 16.0' - 18.0' CLAY 18.0' - 50.0' FINE SAND, WATER TABLE @ 10.0'	SOIL BORING NO. 3 0.0' - 1.0' TOPSOIL W/GRAVEL 1.0' - 4.0' GRAVEL W/CLAY 4.0' - 10.0' SAND AND GRAVEL 10.0' - 17.0' GRAVEL 17.0' - 27.0' MEDIUM-FINE SAND 27.0' - 50.0' FINE SAND, WATER TABLE @ 30.0'	SOIL BORING NO. 4 0.0' - 1.0' TOPSOIL W/GRAVEL 1.0' - 6.0' GRAVEL W/CLAY 6.0' - 18.0' GRAVEL 18.0' - 32.0' MEDIUM-FINE SAND 32.0' - 50.0' FINE SAND, WATER TABLE @ 32.0'	SOIL BORING NO. 5 0.0' - 1.0' TOPSOIL 1.0' - 2.5' CLAY AND GRAVEL 2.5' - 17.0' SAND AND GRAVEL 17.0' - 34.0' MEDIUM FINE SAND 34.0' - 50.0' FINE SAND, WATER TABLE @ 34.0'	SOIL BORING NO. 6 0.0' - 4.0' FINE SAND, MET 4.0' - 6.0' CLAY 6.0' - 25.0' FINE SAND, WATER TABLE @ 10.0'	SOIL BORING NO. 7 0.0' - 10.0' SAND AND GRAVEL 10.0' - 25.0' GRAVEL 25.0' - 45.0' FINE SAND, WATER TABLE @ 25.0'	SOIL BORING NO. 8 0.0' - 15.0' SAND AND GRAVEL 15.0' - 23.0' FINE SAND 23.0' - 25.0' CLAY	SOIL BORING NO. 9 0.0' - 17.0' SAND AND GRAVEL 17.0' - 20.0' CLAY
--	--	---	--	--	---	--	---	--

- GENERAL NOTES**
- PROPERTY DESCRIPTION**
70-14-03-100-017
PART OF NW FRL 1/4 COM AT W 1/4 COR, TH E 1450.54 FT TO PT OF BEG, TH N 03D 19M 44S W 346 FT, E 33.06 FT, TH N 03D 19M 44S W 1355.78 FT ALG CEN LI OF 22ND AVE, TH NE'LY 73.55 FT ALG A 47 FT RAD CURVE TO LEFT (CHD BEARS N 48D 09M 32S W 66.27 FT), S 87D 0M 40S W 81.28 FT, TH N 03D 19M 44S W 949.35 FT ALG W LI OF E 1/2 OF NW FRL 1/4, TH S 89D 45M 36S E 1327.37 FT ALG N SEC LI TO N 1/4 COR, TH S 03D 55M 55S E 2687.31 FT ALG N&S 1/4 LI TO CEN 1/4 COR, TH W 1260.22 FT ALG E&W 1/4 LI TO BEG. SEC 3 T6N R13W 77.79 AC
 - MAPPING:**
a) Boundary information is based on available remanentation and sectional information by Excel Engineering, Inc.
b) 2 foot interval existing ground contours and topographical features are based on aerial survey photography provided by existing Ottawa County G.I.S.
c) Existing utilities and adjacencies are based on available records.
d) This site is located within the 100 Year Flood Plain, based on the National Flood Insurance Program Rate Maps.
 - ZONING:** Existing classification is "RR"
District regulations:
Front setback = 40 ft.
Side yard = 20 ft.(40 ft. total)
Rear yard = 50 ft.
Lot area = 30,000 sq.ft.
Lot width = 200 ft.
 - EXISTING LAND USE:** Mineral Mining
 - PROPOSED IMPROVEMENTS:**
a) All sand mineral removal operations are subject to restrictions in the Georgetown Township Mineral Mining Ordinance beginning with Section 6(e)XVIII.
b) Traffic flow will be from the intersection of Fillmore Street and Cottonwood Drive to either the West or Southeast.
c) No additional buildings will be placed on the site. Existing buildings may be removed in the future. Current gravel processing equipment will be used and in the future will be moved to the SE corner of the property.
d) Where adjoining parcels are operating under existing gravel extraction permits, the gravel extraction limits will be the property lines. No cut or excavation will be made closer than 50' to any other property line.
e) That portion of gravel access roads within the area of operation will maintain dust control by a water truck on an as needed basis.
f) The completion of mining operation is anticipated to be 10 years with final reclamation to follow.

GENERAL NOTES:
1. PHOTO DATE = 2018

BENCHMARK ELEVATION: 599.95
CENTER OF SECTION REFERENCE POINT
SECTION 2, T6N, R13W GEORGETOWN TWP.



OVERALL MINERAL MINING PLAN
HUIZENGA GRAVEL
FOR: HUIZENGA GRAVEL
ATTN: MR. BILL HUIZENGA
PO BOX 245
ZEELAND, MI 49464

IN: PART OF THE W 1/2, SECTION 2, T6N, R13W,
GEORGETOWN TOWNSHIP, OTTAWA COUNTY, MICHIGAN


REVISIONS:	excel engineering, inc. planners - engineers - surveyors 5252 Clyde Park, S.W. • Grand Rapids, MI 49509 Phone: (616) 531-3660 Fax: (616) 531-2121 www.excelengineering.com
7/27/20 REV PER OWNER & 6/11 TWP LETTER 03-20-20 REV FOR MINING PERMIT EXTENSION 09-15-2010 REV. PER. TWP.	DRAWN BY: MK APPROVED BY: DDG FILE NO.: 911516E
	PROJ. ENG.: DDG PROJ. SURV.: DATE: 03-19-10
	SHEET 1 of 1

P:\Projects\191091151\03\Drawings\091151_2019 Mining.dwg - HUIZENGA, T:\2020\7.22.20 AM .ipof

P:\Projects\19911911516\Drawings\dwg\1911516_2019_Minino.dwg_PHASING_7/16/2020 7:47:34 AM_jroot



AREA	ESTIMATED QUANTITY TO BE MINED
ACTIVE MINING AREA	316,000 CY
FUTURE MINING AREA 1	139,000 CY
FUTURE MINING AREA 2	167,000 CY
FUTURE MINING AREA 3	415,000 CY
TOTAL	1,037,000 CY



PHASING / QUANTITIES HUIZENGA GRAVEL

FOR: HUIZENGA GRAVEL
 ATTN: MR. BILL HUIZENGA
 PO BOX 245
 ZEELAND, MI 49464

exxel engineering, inc.
 planners • engineers • surveyors
 5252 Clyde Park, S.W. • Grand Rapids, MI 49509
 Phone: (616) 531-3660 www.exxelengineering.com

FILE NO.: 911516E DATE: 07/02/2020

Expires	ML#		
	ML1502	Ottawa County Road Commission	OK
	ML1505	J&D Investors LLC	
	ML1501	Grand Rapids Gravel/DeWent	OK
	ML1503	Boynton Gravel	OK
	ML1504	Huizenga Gravel Company/Land LLC	OK
6/30/2021	ML1601	DeWent Gravel	OK
6/30/2018	ML1801	Poortenga Properties	OK
6/30/2019	ML1401	Cedar Valley Associates, Inc.	OK

**Georgetown Charter Township
Mineral Mining**

1515 Baldwin Street, P.O. Box 769
Jenison, MI 49429-0769

Inspection Report Date 11/7/19

Location: 9301 12TH AVE, P.P. # 70-14-02-100-004

Mineral Mining License Number: PML1501 – old 1004-Grand Rapids Gravel/DeWent

Comments: The Code Enforcement Officer conducted a site inspection at the above mining location and has noted the following:

11/7/19: Mining as required: R

**Georgetown Charter Township
Mineral Mining**

1515 Baldwin Street, P.O. Box 769
Jenison, MI 49429-0769

Inspection Report Date 1/7/19

Location: 1551 TAYLOR ST, P.P. # 70-14-02-300-005

Mineral Mining License Number: PML1502 – old 1001-Ottawa County Road
Commission

Comments: The Code Enforcement Officer conducted a site inspection at the above
mining location and has noted the following:

1/7/19: Mining as per D: 22

**Georgetown Charter Township
Mineral Mining**

1515 Baldwin Street, P.O. Box 769
Jenison, MI 49429-0769

Inspection Report Date 11/7/19

Location: 9400 12TH AVE, P.P. # 70-14-02-200-006

Mineral Mining License Number: PML1503 – old 1005-Boynton Gravel

Comments: The Code Enforcement Officer conducted a site inspection at the above mining location and has noted the following:

No active mining
Site complies
RJS

**Georgetown Charter Township
Mineral Mining**

1515 Baldwin Street, P.O. Box 769
Jenison, MI 49429-0769

Inspection Report Date 1/3/19

Location: 1861 FILLMORE ST, P.P. # 70-14-03-200-002

Mineral Mining License Number: ML1504 – old 1006-Huizinga Gravel

Comments: The Code Enforcement Officer conducted a site inspection at the above mining location and has noted the following:

Operate as required. Pd

**Georgetown Charter Township
Mineral Mining**

1515 Baldwin Street, P.O. Box 769
Jenison, MI 49429-0769

Inspection Report Date 1/7/19

Location: 6610 40TH AVE, P.P. # 70-14-20-300-054

Mineral Mining License Number: PML1505 (old-1002) - John Koetje, J & D Investors

Comments: The Code Enforcement Officer conducted a site inspection at the above mining location and has noted the following:

No mining equipment or activity on site
Piles of top soil within development
Most of area being developed. R1

**Georgetown Charter Township
Mineral Mining**

1515 Baldwin Street, P.O. Box 769
Jenison, MI 49429-0769

Inspection Report Date 11/7/19

Location: 1601 CHICAGO DR, P.P. # 70-14-23-100-028

Mineral Mining License Number: ML1601-DeWent Gravel

Comments: The Code Enforcement Officer conducted a site inspection at the above mining location and has noted the following:

Nothing was required. RJ

**Georgetown Charter Township
Mineral Mining**

1515 Baldwin Street, P.O. Box 769
Jenison, MI 49429-0769

Inspection Report Date 1/17/19

Location: 2581 Port Sheldon, P.P. # 70-14-21-400-100 and 21-440-004

Mineral Mining License Number: PML1801 – old 1303-Poortenga Properties

Comments: The Enforcement Officer conducted a site inspection at the above mining location and has noted the following:

No active mining

Top soil storage piles still in place

No grading (R)

**Georgetown Charter Township
Mineral Mining**

1515 Baldwin Street, P.O. Box 769
Jenison, MI 49429-0769

Inspection Report Date 1/3/19

Location: 2511 Fillmore and 9250 28th Ave. P.P. # 70-14-04-200-021

Mineral Mining License Number: PML1401-Cedar Valley Associates

Comments: The Code Enforcement Officer conducted a site inspection at the above mining location and has noted the following:

Area is being mined & copies with plans.

However there is currently no equipment on the site.

RN